



EARTHQUAKE PREPAREDNESS AND RESPONSE

Oklahoma DOT's Proactive Approach for Bridges

PRESENTERS:


WALT PETERS, P.E.
Oklahoma Department of Transportation
Oklahoma City, OK

GREGG A. HOSTETLER, P.E.
Infrastructure Engineers, Inc.
Edmond, OK



April 10, 2018

Project Team



The Problem

MENU

TIME

LATEST

MAGAZINE

VIDEOS



The U.S.'s New Earthquake Capital: Oklahoma

PREDICTIVE ANALYTICS COULD HELP IMPROVE YOUR BUSINESS PERFORMANCE.

Sony World Photography Awards Winners Revealed

Behind TIME's Photo Shoot with Renowned Artist Yayoi Kusama

See Colorized Photos of a Young Queen Elizabeth II

What We Learned From Chris Hondros and Tim Hetherington

See GIFs of New York Voting on Primary Day

LIGHTBOX OKLAHOMA

The U.S.'s New Earthquake Capital: Oklahoma

Josh Sanburn @joshsanburn | March 14, 2016


Photographer John Francis Peters captures how the ground is shifting—both seismically and politically—in Oklahoma






The Problem

Data from US Geological Survey



The Problem



Data from US Geological Survey



The Problem

M5.8 - Pawnee, OK (September 3, 2016)
Largest Quake in Oklahoma History
Cosmetic Bridge Damage



Figure 14: Observations of damage at the West Abutment of Belford Bridge (Latitude/Longitude: (36.505°, -96.8493°)): a,b) concrete spalling of abutment; c) approx. 4 cm wide gap between backfill soil and abutment

The Problem

M5.8 - Pawnee, OK
(Sept 3, 2016) –
Sand Boil

The Geotechnical Aspects of the September 3, 2016 M5.8 Pawnee, Oklahoma Earthquake




Authors:

Patricia Clayton, George Zalachoris, Ellen Rathje (Univ. of Texas at Austin)
Tejo Bheemasetti, Santiago Caballero, Xinbao Yu (Univ. of Texas at Arlington)
Scott Bennett (USGS)





Report Date: October 17, 2016

The Problem





Oklahoma
Seismic
Events for
7-day
period
ending
4/9/2018

Resources and Research



Earthquake Preparedness, Response and Recovery Plan

April 2010



Scope of Work

Phase 1 (May 2015 through August 2016)

- I. Interim Post-Earthquake Bridge Inspection Protocol
- II. ShakeCast-OK Cost/Benefit Analysis
- III. Field Inspection Manual
- IV. Draft Earthquake Response Plan
- V. Training
- VI. Seismic Review of Three Bridges
- VII. Meetings and Senior Staff Briefings

Phase 2 (Started September 2016 - Ongoing)

- I. Final development and implementation of ShakeCast-OK
- II. Update response protocol to incorporate ShakeCast-OK
- III. Update Response Plan and Inspection Manual to incorporate ShakeCast-OK
- IV. Training
 - a) Stage 3 Inspection training
 - b) ODOT management training
- V. Monthly progress meetings



Interim Post-Earthquake Bridge Inspection Protocol

Goal - Build on and refine current ODOT protocol; move to “Smart Inspection Radii” approach



OKLAHOMA DEPARTMENT OF TRANSPORTATION
200 NE 21st Street Oklahoma City, OK 73105 (405) 521-4675

January 22, 2015

To: Field Division Engineers

From: Paul Green, Director of Operations *P. A.*

Re: Earthquake Protocol & Procedures

Please find attached the “ODOT Post Earthquake Inspection Protocol & Procedures”. While we have been following the criteria in this document, it is important that we have a standardized system and a form that can be used statewide to document earthquake event structure. Please share this information with your Bridge Engineer to be inspecting structures for damage after an earthquake event. ODOT’s official guidance for Earthquake Protocol & Procedures has been developed and accepted for implementation.

ODOT – Post Earthquake Inspection Protocol & Procedures

Magnitude

3.0 to 3.9	Inspect at the discretion of the Division Engineer
4.0 to 4.9	Inspect Bridges within a 5 Mile radius of Epicenter*
5.0 to 5.5	Inspect Bridges within a 25 mile radius of Epicenter*
5.6 or larger	Inspect Bridges within a 50 Mile radius of Epicenter*


*Increase radius at 5 mile increments if damage found

Interim Post-Earthquake Bridge Inspection Protocol

Smart Inspection Radii – Overview


- Within what distance from the earthquake epicenter do we expect demand to exceed capacity?

CAPACITY




∧

DEMAND




Interim Post-Earthquake Bridge Inspection Protocol



Capacity – Fragility Curves

Interpretation: For a given level of shaking, what level of damage is expected?



Interim Post-Earthquake Bridge Inspection Protocol


Capacity – Fragility Curves

- HAZUS gives fragility curves for “standard bridges” adjusted for:

- Year built
- Number of spans
- Skew angle
- Main span material
- Total bridge length


- Inspection deemed necessary for $S_1 > 5.56\%g$

- Input from Caltrans (California DOT)
- Comparison of CA to non-CA bridges in HAZUS




Trigger
Value

Interim Post-Earthquake Bridge Inspection Protocol




Prioritizing Bridge Inspection:
Higher priority for fracture
critical, structurally deficient,
and variable skew bridges.



Phase 1 - Task I

Interim Post-Earthquake Bridge Inspection Protocol



5.56%
Trigger Value


Demand – Ground
Motion Intensity

USGS provides maps of
ground-motion intensity
after an earthquake


Interim Post-Earthquake Bridge Inspection Protocol

Demand – Ground Motion Prediction

Campbell (2003)
tends to over
predict ground
motions




Interim Post-Earthquake Bridge Inspection Protocol



Calibrated Campbell (2003)
Ground Motion Prediction
Equation (GMPE) for Oklahoma
station data – Magnitude of the
earthquake plus the bias factor
yields the best fit to the station
data

Interim Post-Earthquake Bridge Inspection Protocol



Interim Post-Earthquake Bridge Inspection Protocol

- Combining capacity and demand analysis gives the proposed inspection radii

Smart Radii Inspection Protocol

Previous ODOT Protocol

Magnitude Range	Inspection Radius (miles)
4.0 to 4.9	5
5.0 to 5.5	25
5.6 +	50

Magnitude Range

Inspection Radius (miles)

4.4 to 4.7

5

4.8 to 5.3

15

5.4 to 5.8

30

5.9 to 6.2

60

6.3 +

120

*Radius increased at discretion of Division Engineer;
i.e. to account for USGS location uncertainty*

ShakeCast-OK Cost/Benefit Analysis

ShakeCast – Web-based application developed by USGS and Caltrans for situational awareness following an earthquake.

Benefits:

- ✓ Improved ground-motion prediction
 - ✓ Reduction in frequency of triggered responses
 - ✓ Less bridges flagged for inspection than with radius based protocol
- ✓ Automated inspection prioritization
- ✓ Streamlined inspection mobilization

Costs:

- ✓ Installation and hosting costs
- ✓ Maintenance and upkeep

Field Inspection Manual




Table of Contents	
1. Introduction.....	1
2. Personnel Qualifications.....	2
3. Planning.....	3
4. Safety.....	3
5. Communication.....	4
6. Equipment Needs.....	4
7. Inspection Forms.....	6
8. Bridge Terminology and Typical Oklahoma Bridges.....	8
8.1 Deck.....	11
8.2 Superstructure.....	12
8.3 Substructure.....	15
9. Post-Earthquake Inspection Guidance.....	21
9.1 Roadway Approaches and Deck.....	30
9.2 Nonstructural Elements.....	31
9.3 Superstructure.....	34
9.4 Substructure.....	35
9.5 Geotechnical Problems.....	37
9.6 Skewed Structures.....	45
10. Inspection Procedures.....	48
10.1 Stage 1 Inspection.....	51
10.2 Stage 2 Inspection.....	51
APPENDICES	
APPENDIX 1 - Glossary.....	53
APPENDIX 2 - References.....	54
APPENDIX 3 - List of Figures.....	57
	58

i

Field Inspection Manual

The intent of the manual is to:

- ✓ Prepare personnel to properly assess and report bridge earthquake damage
- ✓ Define personnel qualifications, responsibilities, and recommended equipment
- ✓ Discuss inspection personnel safety
- ✓ Establish inspection procedures and provide clear guidance on what to look for
- ✓ Define basic bridge terminology; illustrate common bridge types and components
- ✓ Illustrate typical examples of post-earthquake bridge damage
- ✓ Provide standard post-earthquake inspection forms
- ✓ Define and describe stages of response
- ✓ Describe appropriate inspection follow-up actions



Field Inspection Manual

Stage 1 Inspection

- Completed immediately after an earthquake for assigned bridges
- Quick, accurate ground level safety evaluation
- Categorize bridges as:
 - Green – Safe
 - Yellow – Minor damage
 - Red – Bridge Closed




Figure 120: Stage 1 Inspection flowchart

Field Inspection Manual

Stage 2 Inspection

- Initiated when “Further Evaluation Required” requested by Stage 1 inspector
- Team typically deployed within 8 hours or less
- “Hands-on” assessment, requiring specialized access
- May only include portions of the bridge
- Categorize bridges as:
 - Green – Safe
 - Yellow – Minor damage
 - Red – Bridge Closed



Field Inspection Manual

Stage 3 Inspection

- Specialized assessment
- Focus is restoring service to closed or otherwise restricted bridge
- “Hands-on” assessment, requiring specialized access
- Team comprised of:
 - Structural Engineer
 - Geotechnical Engineer
 - Certified Bridge Inspector



Phase 1 - Task III

Field Inspection Manual

STAGE 1 - POST-EARTHQUAKE INSPECTION FORM



OKLAHOMA DEPARTMENT OF TRANSPORTATION

Inspector(s): BOB INSPECTOR MR. PERFECT

Date: 1/11/2016 Division: 3

Event ID: 0111-08-01

General Comments: UNEVEN ROADWAY APPROACHING BRIDGE

Bridge ID No.:	Structure No.:	No	Yes	F.E.R.	Needs To Be Closed	Span Collapse	Partial Collapse	Approach Roadway Damage	Deck Damage (Expansion Joints, Rails, Parapets)	Superstructure Damage (Girders, Diaphragms, Stringers)	Bearing Damage	Substructure Damage (Piers, Pier Caps, Abutments, Wingwalls)	Soil Problems (Geotechnical)	Non-Structural Elements (Utilities)
<u>17594</u>	<u>4603</u>	☒	☐	☐	☐	☒	☒	☒	☒	☒	☒	☒	☒	☒


*F.E.R.: Further Evaluation / Stage 2 Inspection Required

OVERALL RATING

☐ Green (Safe) ☐ Yellow (Minor Damage) ☒ Red (Bridge Closed)

Observations:

- SETTLED ROADWAY APPROACH AT SOUTHEAST CORNER
- BROKEN UTILITY PIPE AT EAST SIDE OF NORTH ABUTMENT.
- SPALLED CONCRETE AT SOUTH END OF NORTH ABUTMENT.
- SPALL AT WEST END OF Pier 2 WITH EXPOSED REBAR
- WALL AT Pier 4 IS COLLAPSED.



Labels: Rails and Parapets, Deck, Expansion Joints, Approach, Wingwall, Abutment, Bearings, Pier Cap and Column, Girder

STAGE 2 - POST-EARTHQUAKE INSPECTION FORM (1 OF 2)

Inspector(s): BOB INSPECTOR MR. SMART

Date and Time of Arrival: 04/11/2016 9:30am Departure Time: 11:30 AM

Bridge ID No.: 18758 Structure No.: 4603 1838ER

Bridge Type: STEEL GIRD Route: 66 Intersects: US-266



Overall Damage

☒ Minor ☐ Severe

☐ Moderate ☐ Collapsed

☐ None ☐ None

1. APPROACH ROADWAYS

☐ Excessive Settlement

☐ Excessive Transverse Movement

☐ Approach Slab Off Bridge Seat

☒ Misalignment

☐ Other (Specify): _____

Damage: ☐ None ☒ Minor ☐ Moderate ☐ Severe

Comments: THE SOUTH APPROACH IS MISALIGNED HORIZONTALLY UP TO 1".

Photograph ID: 3128

2. DECK

☐ Joint Displacement

☐ Deck Cracked / Spalled

☐ Damaged Non-Structural Elements (Lighting, Utilities)

☐ Misalignment

☐ Damaged Parap

☐ Displacement /

☐ Other (Specify): _____

Damage: ☐ None ☒ Minor ☐ Moderate

Comments: NO EQ DAMAGE WAS FOUND. - WIDESPREAD MAP CRACKING (UP TO 1/16") TYPICAL - SPALLS AT RANDOM LOCATIONS

3. SUPERSTRUCTURE

Beams/Girders/Floorbeams/Stringers ☐ Concrete ☒ Steel

☐ Flexural / Shear Cracks (circle type(s) that apply)

☐ Concrete Spalling

☐ Local Buckling

☐ Partially Dropped Span

☐ Fracture

☐ Connection Failure

☐ Plastic Deformation

☐ Displacement /

☐ Diaphragm / Br

☐ Other (Specify): _____

Damage: ☒ None ☐ Minor ☐ Moderate

Comments: NO EQ DAMAGE FOUND

Steel Truss Members

☐ Local Buckling (Specify): _____

☐ Connection Failure (Specify): _____

☐ Displacement /

☐ Fracture (Speci

☐ Other (Specify): _____

Damage: ☐ None ☐ Minor ☐ Moderate

Comments: N/A

STAGE 2 - POST-EARTHQUAKE INSPECTION FORM (2 OF 2)

4. BEARINGS

Type: ☐ Rocker ☐ Roller ☒ Elastomeric ☐ Other _____

☐ Failure

☐ Excessive Movement

☐ Sheared / Pullout of Bolts

☐ Topped

☐ Other (Specify): _____

Damage: ☐ None ☒ Minor ☐ Moderate ☐ Severe

Comments: THE BEARINGS AT THE SOUTH ABUTMENT HAVE DEFORMED A MAX OF 1" AFTER EARTHQUAKE LOADING.

Photograph ID: _____

5. SUBSTRUCTURE

Piers

☐ Flexural / Shear Cracks (circle type(s) that apply)

☐ Spalling

☐ Local Buckling

☐ Settlement

☐ Foundation Movement

☐ Other (Specify): _____

Damage: ☒ None ☐ Minor ☐ Moderate ☐ Severe

Comments: NO EARTHQUAKE DAMAGE WAS FOUND.

Photograph ID: _____

Abutments

☐ Flexural / Shear Cracks (circle type(s) that apply)

☐ Wall Movement/Rotation

☐ Backfill Settlement

☐ Foundation Movement

☐ Other (Specify): _____

Damage: ☒ None ☐ Minor ☐ Moderate ☐ Severe

Comments: NO EARTHQUAKE DAMAGE FOUND

Photograph ID: _____

6. GEOTECHNICAL

☐ Slope Failure

☐ Lateral Spreading of Slopes

☐ Liquefaction

☐ Other (Specify): _____

Damage: ☒ None ☐ Minor ☐ Moderate ☐ Severe

Comments: _____

Photograph ID: _____

ACTION

☐ Repair Request: _____

☐ Further investigation required (Specify): _____

Recommendations: MONITOR ELASTOMERIC BEARINGS TO VERIFY NO DAMAGE IS HELD WHEN DEEMED BY DIVISION ENGINEER

OVERALL RATING ☒ Green (Safe) ☐ Yellow (Limited Access) ☐ Red (Bridge Closed)

Field Inspection Manual



Figure 62: Approach slab settlement and cracking of the concrete barrier (*NISEE*)

 **ACTION:** May require closure. Inspect for settlement and superstructure or substructure damage. Further evaluation is required.



Figure 63: Settlement of the approach slab (*NYSDOT*)

 **ACTION:** Close bridge. Report findings immediately.

Field Inspection Manual



Figure 68: Vertical displacement observed in expansion joint (*NISEE*)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.




Figure 69: Transverse joint movement (*NYSDOT*)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.

Field Inspection Manual



Figure 76: Damage to beam caused by movement of the structure (*NISEE*)

 **ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.**



Figure 77: Superstructure spalled at bearing location (*NISEE*)

 **ACTION: Report findings and recommend Stage 2 Inspection.**

Field Inspection Manual



Figure 78: Rocker bearing failure (*NISEE*)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.



Figure 79: Failure of bearing, complete lateral displacement (*NISEE*)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.




Figure 73: Severely spalled concrete beams, significant flexural cracks (*NISEE*)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.



Figure 74: Cracking in web of concrete beams (*NYSDOT*)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.

Field Inspection Manual



Figure 86: Cracking and rotation of wingwall (NISEE)

ACTION: Close bridge. Report findings and immediately request Stage 2 Inspection.



Figure 87: Wingwall released from superstructure after earthquake tremors (NISEE)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.



Figure 92: Full collapse of pier (NISEE)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.



Figure 93: Failure of column (NISEE)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.

Field Inspection Manual



Figure 94: Shear cracks in column (*NISEE*)

ACTION: Bridge remains open. Report findings immediately and request Stage 2 Inspection.



Figure 95: Compression failure on the top of concrete bridge pier (*INDOT*)

ACTION: Report findings immediately and request Stage 2 Inspection.



Figure 96: Confinement failure in single column (*NISEE*)

ACTION: Close bridge. Report findings immediately and request Stage 2 Inspection.



Figure 100: Ground movement indicating possible foundation problems (*INDOT*)


ACTION: Report findings immediately and request Stage 2 Inspection.



Figure 102: Liquefaction sand boil

ACTION: Report findings immediately and request Stage 2 Inspection. Close bridge when sand boils are present near substructure.

Draft Earthquake Response Plan



The intent of the response plan is to:

- ✓ Educate personnel on earthquake fundamentals and Oklahoma seismicity
- ✓ Provide a clear & concise earthquake response protocol
- ✓ Define levels of response & stages of inspection
- ✓ Outline minimum qualifications and training for response personnel
- ✓ Provide guidance on temporary shoring and repair techniques

Training – Stage 1

Learning Outcomes:


- ✓ Understand ODOT's Post-Earthquake Bridge Inspection Manual
- ✓ Define the qualifications and role of the Stage I inspector
- ✓ Define basic bridge terminology and identify Oklahoma common bridge types and components
- ✓ Describe ODOT's Stage I inspection process
- ✓ List safety concerns for post-earthquake inspections



Training – Stage 1

ODOT Division or Other Agency	Training Date	Start Time	Finish Time	# Participants		
				ODOT	Other	Total
ODOT Division 4	June 22, 2016	8:00 a.m.	11:30 p.m.	29	24	53
ODOT Division 3	July 13, 2016	10:00 a.m.	3:00 p.m.	21	0	21
ODOT Division 5	July 27, 2016	8:30 a.m.	12:00 p.m.	22	0	22
ODOT Division 1	August 17, 2016	8:30 a.m.	12:00 p.m.	29	6	35
ODOT Division 8 Session 1	August 18, 2016	8:30 a.m.	12:00 p.m.	52	0	52
ODOT Division 8 Session 2	August 18, 2016	1:00 p.m.	4:30 p.m.	24	2	26
ODOT Division 7	August 25, 2016	8:00 a.m.	11:30 a.m.	24	20	44
ODOT Division 6	September 15, 2016	9:00 a.m.	12:30 p.m.	28	4	32
ODOT Division 2 Session 1	September 22, 2016	8:00 a.m.	11:30 a.m.	17	17	34
ODOT Division 2 Session 2	September 22, 2016	1:00 p.m.	4:30 p.m.	16	5	21
Oklahoma Turnpike Authority	September 22, 2016	1:00 p.m.	4:30 p.m.	0	37	37
USACE Tulsa	September 22, 2016	1:00 p.m.	4:30 p.m.	0	18	18
Totals				262	133	395

**Organization -
Eight Field Divisions and a
Central Office**



Training – Stage 2

Learning Outcomes:

- ✓ Understand ODOT's Post-Earthquake Bridge Inspection Manual
- ✓ Define the qualifications and role of the Stage II inspector
- ✓ Describe ODOT's Stage II inspection process
- ✓ List safety concerns for post-earthquake inspections



OKLAHOMA DOT POST-EARTHQUAKE
Stage II Inspection Training
Program Overview and Safety

TRAINING DATE: 05/24/2016	INSTRUCTOR: Gregg Hostetler
-------------------------------------	---------------------------------------


INFRASTRUCTURE
ENGINEERS, INC.

Approximately 200 NBIS & ODOT certified bridge inspectors received training during ODOT's Annual QCQA Workshop.

Seismic Review of Three Bridges

- I-35 over Canadian River (top)
- I-35 over Cimarron River (bottom right)
- SH-11 over I-35 (bottom left)



Seismic Review of Three Bridges

Key findings:

- Validation of S_1 trigger values
- Very low potential for liquefaction
- Bearings are most vulnerable to damage
- Transverse loading most critical
- Cost per bridge for site specific analysis:
 - \$21k for geotechnical
 - \$15k for structural



Phase 1 - Task VII

Meetings and Senior Staff Briefings


EC-1609 – Post-Earthquake Inspection Guidelines
Progress / Team Strategy Meeting
April 11, 2016

Attendees:

Initials	Name/Organization	Phone	E-mail
A.J.	Abraham Jauregui (IEI)	(415) 794-6030	ajauregui@go-iei.com
	Bill Wilkinson (ODOT)	(580) 332-1526	bwilkinson@odot.org
	Casey Shell (ODOT)		cshell@odot.org
DK	Dan Knickmeyer (ODOT)	(405) 521-4009	dknickmeyer@odot.org
GH	Gregg Hostetler (IEI)	(405) 227-0531	ghostetler@go-iei.com
IK	Ivanna Kaid Bay (OU)		i.kaidbay@ou.edu
JP	Joshua Pogue (ODOT)	(918) 323-6900	jpogue@odot.org
KR	Karthik Radhakrishnar (Kleinfelder)	(918) 549-8121	karthik@kleinfelder.com
MM	Matt Mitchell (ODOT)	(405) 436-5173	mmitchell@odot.org
MR	Muralee Muraleetharan (OU)	(405) 325-4247	muralee@ou.edu
	Paul Green (ODOT)	(405) 521-4675	pdgreen@odot.org
	Randy Leonard (FHWA)	(405) 254-3331	Randall.leonard@odot.org
SH	Samantha Heinrich (OU)	(618) 420-3405	Samantha.k.Heinrich-1@ou.edu
SH	Scott Harvey (OU)	(405) 325-3836	harvey@ou.edu
SA	Steven Jacobi (ODOT)	(405) 521-2606	sjacobi@odot.org
	Tim Tegeler (ODOT)	(405) 521-6916	ttegeler@odot.org
TLT	Tracy Terrill (ODOT)	(580) 255-7586	tterrill@odot.org
WP	Walt Peters (ODOT)	(405) 521-2606	wpeters@odot.org
WK	Wes Kellogg (ODOT)	(405) 522-2606	wkkellogg@odot.org
ZZ	Zia Zafir (Kleinfelder)	916-366-2382	zzafir@kleinfelder.com
	David Jarvis (USACE)		David.jarvis@usace.army.mil
	Jeff Roberts (USACE)		Jeffery.m.roberts@usace.army.mil
JB	Jeremy Boak (OGS)	(405) 325-7968	jboak@ou.edu
	Christopher R. Narice (ODOT)	405 522-4998	c.narice@odot.org




ShakeCast-OK



Phase 2 – Task I

ShakeCast-OK


Test of Oklahoma ShakeCast
based on M5.8 in Pawnee, OK
Note: Report includes
Oklahoma 5 Digit NBI No., Str.
No., & location



Phase 2 – Task I


ShakeCast-OK

M5.6 - Prague, OK (Nov 6, 2011)



- Old Protocol (50 miles): 772 bridges
- Interim Protocol (30 miles): 189 bridges
-  ShakeCast: 32 bridges

M5.8 - Pawnee, OK (Sept 3, 2016)



- Old Protocol (50 miles): 366 bridges
- Interim Protocol (30 miles): 167 bridges
-  ShakeCast: 38 bridges



WALT PETERS, P.E.
wpeters@odot.org
(405) 521-2606



INFRASTRUCTURE
ENGINEERS, INC.

ingenuity & agility

GREGG A. HOSTETLER, P.E.
ghostetler@go-iei.com
(405) 227-0531

QUESTIONS



NATIONAL BRIDGE PRESERVATION PARTNERSHIP CONFERENCE 2018

PRACTICES WE CAN NOT AFFORD TO DEFER